# BRUHAT BANGALORE MAHANAGAR PALIKE

## Project Division, Yelahanka Zone

## SCHEDULE - B

**Name of Work : Improvements to footpath and drains at Park HMT Layout in Ward No. 09 Vidyaranyapura**

| SNo | Quantity | Item Name | Unit | | |
|---|---|---|---|---|---|
| | | | | In figures | In words |
| 1 | 50.31 | KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 Page No. 143 Item No. 19.1, PWD SR 2018-19 | Cum | 250.24 | Rupees Two Hundred Fifty And Paise Twenty Four Only |
| 2 | 90.19 | Removing & Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 27 Item No. 5.33, PWD SR 2018-19 | Sqm | 111.30 | Rupees One Hundred Eleven And Paise Thirty Only |
| 3 | 79.58 | Providing granite slabs of selected quality roughly dressed having a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete. Page No. 27 Item No. 5.31.1, PWD SR 2018-19 | Sqm | 742.00 | Rupees Seven Hundred Forty Two Only |
| 4 | 2.43 | KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. MORTH Specification No. 2100 Page No. 222 Item No. 27.18, PWD SR 2018-19 | Cum | 5421.90 | Rupees Five Thousand Four Hundred Twenty One And Paise Ninety Only |
| 5 | 8.64 | KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar, stone hammered dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13, cement mortar 1:6 KBS 5.1.13 Page No. 25 Item No. 5.6, PWD SR 2018-19 | Cum | 4871.76 | Rupees Four Thousand Eight Hundred Seventy One And Paise Seventy Six Only |
| 6 | 21.77 | KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No. 13 Item No. 4.6, PWD SR 2018-19 | Cum | 5747.32 | Rupees Five Thousand Seven Hundred Forty Seven And Paise Thirty Two Only |

Executive Engineer
Project Division
Yelahanka Zone

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Contractor

| | Quantity | Item Name | Unit | | |
|---|---|---|---|---|---|
| | | | | In figures | In words |
| | 78.80 | KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 Page No. 27 Item No. 5.26.1, PWD SR 2018-19 | Sqm | 1019.72 | Rupees One Thousand Nineteen And Paise Seventy Two Only |
| 8 | 78.80 | KSRB 5-15 : Providing and constructing non load bearing wall with solid concrete blocks of size 400x100x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 Page No. 27 Item No. 5.28, PWD SR 2018-19 | Sqm | 859.66 | Rupees Eight Hundred Fifty Nine And Paise Sixty Six Only |
| 9 | 80.80 | KSRB 5-15 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 Page No. 27 Item No. 5.26.2, PWD SR 2018-19 | Sqm | 859.66 | Rupees Eight Hundred Fifty Nine And Paise Sixty Six Only |
| 10 | 324.00 | Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate) | Sqm | 2337.00 | Rupees Two Thousand Three Hundred Thirty Seven Only |
| 11 | 16.20 | Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate) | Sqm | 5418.00 | Rupees Five Thousand Four Hundred Eighteen Only |
| 12 | 887.00 | Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. Page No. 27 Item No. 5.30, PWD SR 2018-19 | Nos | 432.48 | Rupees Four Hundred Thirty Two And Paise Forty Eight Only |

EXECUTIVE ENGINEER-I

Executive Engineer
Project Division
Yelahanka Zone

| | uantity | Item Name | Unit | In figures | In words |
|---|---|---|---|---|---|
| | 119.70 | KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Page No. 124 Item No. 15.80, PWD SR 2018-19 | Sqm | 39.22 | Rupees Thirty Nine And Paise Twenty Two Only |
| 14 | 119.70 | KSRB 15-19.2 : Providing and applying spray painting (excluding priming coat ) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. spray painting in two coat. Page No. 124 Item No. 15.82, PWD SR 2018-19 | Sqm | 90.10 | Rupees Ninety And Paise Ten Only |

04/3/19

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Contractor

Executive Engineer
Project Division
Yelahanka Zone